

**QUOTE FORM**  
**TOM GREEN COUNTY TXCDBG 712369**  
 Page 1 of 2

**COMPANY NAME:** Landers Septic + Concrete

**BASE WORK SCOPE (required)**

The TCEQ/OSSF permit fee is a standard rate of \$210 per system. Please include this fee in your price.

Item	NAME	ADDRESS	TYPE OF OSSF	PRICE
1.	Mary Necessary	4217 Anson St	750 g tank, 110 linear feet drainfield	\$10,500
2.	Debra Henry	10042 Caribou Trail	1000 gallon tank, 180 linear feet drainfield	\$9,000

The base, none, one, or more alternates may be awarded in any combination.

**TOTAL OF ALL BASE, ITEMS 1-2** \$ 19,500

**Alternate 1**

Item	DESCRIPTION	QUANTITY	UNIT PRICE	PRICE
A-1	Plug existing well (per TCEQ requirements)	1 LS	1200	\$1200

The base, none, one, or more alternates may be awarded in any combination.

**TOTAL OF ALL ALTERNATE, ITEMS 1** \$ 1200

The undersigned certifies that the prices contained in this proposal have been carefully checked and are submitted as correct and final. The undersigned agrees that time is an essential element of the contract. It is also agreed that each day of delay beyond the number of calendar days herein agreed upon for completion of the Project shall be acted upon as herein stipulated. Furthermore, both the Owner (Tom Green County) and the Installer are in agreement that each such day of delay, the Owner may withhold, permanently from the undersigned's total compensation, the sum of Two Hundred Dollars (\$200) per calendar day as LIQUIDATED DAMAGES for such delay.

**Installer's Signature:** 

**QUOTE FORM**  
**TOM GREEN COUNTY TXCDBG 712369**  
**Page 2 of 2**

**SPECIFICATION NOTES**

OSSF installation for existing residential single family property shall be in accordance with site evaluations and designs provided by the County prior to notice to proceed. Specifications reflect typical system and additional sample evaluations are provided with this small purchase package.

1. OSSF will be installed in accordance with scaled drawings provided for each installation and will maintain normal setbacks from residential structures, property lines, and existing water wells (if any). Installer shall be responsible for proper disposal of any excavated soils and take measures to decontaminate any contaminated soils prior to removal from site in accordance with state and county requirements. Any trees that obstruct the application area shall be removed. Areas that are bare or disturbed must be seeded or sodded with Bermuda/rye grass mix prior to system operation.
2. All existing septic tanks on property shall be pumped by a TCEQ licensed pumper and disposed of according to local, state and federal regulations, lids collapsed, and backfilled with soil.
3. Water lines may not readily locatable and could be encountered in close proximity to the OSSF. Minimum separation distances (30 TAC 285) must be maintained by re-routing or encasement with schedule 40 PVC to maintain the required setback. All OSSF supply lines crossing driveways must be encased with schedule 40 PVC. All house plumbing (shower, wash water, discharge lines, etc.) must be connected to the new OSSF. Please consider this in your unit price.
4. If needed, electrical breaker box must have separate breaker available for OSSF pump. Please consider this in your unit price.

**Company Name:** Landers Septic + Concrete

**Installer Name (if other than above):** Layton Landers

**Full Address:** 8917 N Hwy 87

**Phone:** 325-658-5079

**TCEQ Registration Number:** OS 0030277

**EIN or SSN:** 75-2609173

**Signature:** 